TABLE OF BULK REQUIREMENTS

DISTRICT REGULATIONS	REQUIRED	PROPOSED	COMMENTS
ZONING DISTRICT	C-1	C-1	NO CHANGE
MINUMIN LOT AREA	5,000 SF	8,615.6 SF	NO CHANGE
MINIMUM LOT WIDTH	50 FT	115.31 FT	NO CHANGE
MINIMUM LOT DEPTH	100 FT	84.00 FT	NO CHANGE
MINIMUM FRONT YARD SETBACK	5 FT	34'-4" FT	NO CHANGE
MINIMUM SIDEYARD SETBACK	0/0 FT	6'-4" / 37'-2" FT	NO CHANGE
MINIMUM REARYARD SETBACK	20 FT	5 FT	NO CHANGE
MAXIMUM BUILDING HEIGHT	2 1/2 ST	2 ST	ADD 1 STORY
MAXIMUM BUILDING HEIGHT	35 FT	28' FT	ADDED 12 FT
MAXIMUM BUILDING COVERAGE	75%	22%	NO CHANGE



NORTH

SITE PLAN

SCALE: 1" = 10'-0"

NOTES:
1. SIDES AND REAR SETBACKS TO EXISTING BUILDING REMAIL THE SAME AS PRIOR TO CONSTRUCTION.
2. SETBACK TO REAR PROPERTY LINE IS REDUCED BY 3'-10 AT SECOND FLOOR PORCH FLOOR AND 4'-5 AT ROOF OVERHANG.
3. ACCESSABLE ROUTE, PARKING AND RAMPS (SIDEWALKS) SHALL ALL MEET THE REQUIREMENTS OF 4.1, 4.6 AND 4.8 OF ADAAG's ADA ACCESSIBILITY REQUIREMENTS
4. CROSS SLOPE ON RAMPS AND SIDEWALKS SHALL NOT EXCEED 1:50 OR 2% SLOPE. ANY PART OF THE ACCESSIBLE ROUTE OF TRAVEL GREATER THAN 1:20 SHALL MEET THE REQUIREMENTS FOR A RAMP.
5. PARKING LAYOUT, SIZE AND ARRANGEMENT SHALL COMPLY WITH SECTION 4.6 SUB-ARTICLES 4.6.1 TO 4.6.2.
6. RAMPS AMD SIDEWALKS SHALL COMPLY WITH SECTION 4.8 SUB-ARTICLES 4.8.1 TO 4.8.8.
7. ALL SITE LIGHTING SHALL BE BUILDING MOUNTED. LIGHTING ON THE WESTERN AVENUE FACE OF BUILDING SHALL BE MOUNTED ON THE UNDERSIDE OF PORCH AND ROOF OVERHANG.
8. ALL PLANTING ALONG THE EASTERN PROPERTY LINE SHALL BE SEMI PERMANENT DISPLAY PLANTING ARRANGED TO ACCENTUATE THE LANDSCAPING BUSINESS.
10. EXISTING FIRST FLOOR FOOTPRINT REMAINS 1,950 GROSS SQUARE FEET. NO CHANGE IN FLOOR AREA. THE NEW SECOND FLOOR IS 1,950 GROSS SQUARE FEET. ALL OCCUPANCIES OF THE BUILDING SHALL BE "B" BUSINESS.

PARKING REQUIREMENTS:

ONE (1) SPACE PER 300 SQUARE FEET.	
EXISTING BUILDING AREA	1,950 SQUARE FEET
PROPOSED NEW SECOND FLOOR AREA	1,950 SQUARE FEET
TOTAL PROPOSED AREA	3,900 SQUARE FEET
REQUIRED PARKING	13 SPACES
ALLOWABLE OFF SITE (STREET) SPACES	5 SPACES
PROVIDED ON SITE SPACES	8 SPACES

PARKING NOTE:
OF THE EIGHT (8) ON SITE SPACES PROVIDES ONE SPACE SHALL BE ACCESSABLE



VICINITY MAP



SITE LOCATION MAP

SITE PLAN APPROVED
BY:
DATE: 10/5/09

© 2009 Navteq © 2009 Microsoft

TO THE BEST OF MY KNOWLEDGE INFORMATION AND BELIEF THE PLANS AND SPECIFICATIONS ARE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE NEW YORK STATE UNIFORM FIRE PREVENTION AND BUILDING CODE AND THE NEW

DATE 8/9/09

TO THE BEST OF MY KNOWLEDGE INFORMATION AND BELIEF THE PLANS AND SPECIFICATIONS ARE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE AMERICAN WITH DISABILITIES ACT (FEDERAL LAW).

DATE 8/9/09

REVISIONS:	BY:
PARKING ADDED JULY 20, 2008	
PORCHES ADDED AUG. 20, 2008	
MH&E REVIEW COMMENTS AUG. 9, 2009	

PETER R. HOFFMANN, ARCHITECT
7 HUDSON BLUFF DRIVE
MARLBORO, NEW YORK 12542
PHONE (845) 527-9476 FAX (845) 236-4293

REGISTERED ARCHITECT
PETER R. HOFFMANN
NO. 024841
STATE OF NEW YORK

SITE PLAN

ALTERATIONS AND ADDITIONS TO THE ZAMBITO AND SONS LANDSCAPING
WESTERN AVENUE, MARLBORO, NEW YORK

DATE: JULY 14, 2008
SCALE: 1" = 10'-0"
DRAWN BY: P.R.H.
JOB # 209-08
SHEET SITE-1
OF SHEETS