



WATER SERVICE CONNECTION DETAIL
N.T.S.



STANDARD CLEANOUT CONNECTION DETAIL
NOT TO SCALE




SEPTIC FIELD PLAN VIEW (SEE SHEET 1 FOR # OF ROWS)
N.T.S.

- NOTES:**
1. FLOW EQUALIZATION DEVICES ARE TO BE USED ON AT THE OUTLET PIPES OF THE DISTRIBUTION BOX, AND SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
 2. DISTRIBUTION BOXES SHOULD BE EXAMINED BETWEEN 6 TO 12 MONTHS AFTER THEY ARE INSTALLED TO DETERMINE IF THEY REMAIN LEVEL AND, IF NECESSARY, TO MAKE ADJUSTMENTS.
 3. FLOW LEVELERS SHALL NOT COMPENSATE FOR MORE THAN 1-1/4 INCH DIFFERENCE IN PIPE ELEVATIONS. IN THIS CASE, THE CAUSE OF ELEVATION DIFFERENCES IS TO BE CORRECTED AND THE FLOW LEVELERS AGAIN INSTALLED AND ADJUSTED.

FLOW LEVELER DETAIL

NOT TO SCALE




TYPICAL CONCRETE SEPTIC TANK

NOTES:


1. TYPICAL PRECAST CONCRETE SEPTIC TANKS, WOODARD CONCRETE PRODUCTS, INC. (PROVIDE WATER TIGHT SEAL AT ANY CONSTRUCTION JOINT.)
2. INLET AND OUTLET JOINTS TO SEPTIC TANK ARE TO BE SEALED WITH A NON-SHRINK MORTAR.
3. TO BE USED FOR A FOUR BEDROOM DWELLING.

SPECIFICATIONS	PRECAST SEPTIC TANKS
Concrete Minimum Strength: 4,000 psi at 28 days Reinforcement: 6"x6"x10ga. Wire Mesh, #4 Rebar Air Entrainment: 5% Construction Joint: Butyl Rubber Sealant Pipe Connection: Polylok Seal (patented) Load Rating: 300 psf Weight = 8,700 lbs for Model ST-1000 Weight = 9,500 lbs for Model ST-1250	MODEL ST-1250 1250 GALLONS WOODARD'S CONCRETE PRODUCTS, INC. 629 LYBOLT ROAD, BALLVILLE, NY 10815 (845) 361-0471 / FAX 361-1050 WWW.WOODARDSCONCRETE.COM



DISTRIBUTION BOX DETAIL - DB-9
NOT TO SCALE

SPECIFICATIONS	PRECAST DISTRIBUTION BOXES
Concrete Min. Strength: 4,000 PSI at 28 days Reinforcement: 6"x6"x10ga. Wire Mesh Air Entrainment: 5% Pipe Connection: Polylok Seal (patented) Load Rating: 300 PSF Weight = 280 LBS	MODEL DB-9 / 8 OUTLET BOX WOODARD'S CONCRETE PRODUCTS, INC. 629 LYBOLT ROAD, BALLVILLE, NY 10815 (845) 361-0471 / FAX 361-1050 WWW.WOODARDSCONCRETE.COM



TOP VIEW

NOTE: INSTALLING THE PIPE TO THE TRENCHES PROVIDES A SUFFICIENT ROOM TO INSURE THAT IF AND WHEN NEEDED OUTLETS ARE ACCESSIBLE WITHOUT DISTURBING THE CAPABLE OF BEING CONNECTED TO THE EXPANSION AREA TRENCHES

NOTE

FIRST OF OR ALL DISTRIBUTION LATERALS ARE TO BE PLACED AT IDENTICAL SLOPES.

TO TRENCH SLOPE 1/16\"/>

SECTION

DISTRIBUTION BOX DB-9 INSTALLATION DETAIL
NO SCALE

NOTE: ALL UNUSED OUTLETS TO BE PLUGGED AND SEALED. PIPE JOINTS TO THE DISTRIBUTION BOX TO BE SEALED WITH APOHATIC MATERIAL OR EQUIVALENT.


THESE PLANS ARE INCOMPLETE UNLESS THEY CONTAIN THE SURVEYOR'S AND/OR ENGINEER'S SIGNATURE AND SEAL WHERE APPLICABLE AND SHEETS THROUGH 3

2/07/13/24 Planning board submission
1/06/03/24 UCHD submission

JOHN V. NOSEK, P.E.
LICENSE NO. 083493

SECTION A-A

NOT TO SCALE



NOTES:
DO NOT INSTALL TRENCHES IN WET SOIL.
RAKE SIDES AND BOTTOM OF TRENCH PRIOR TO PLACING GRAVEL.
END OF ALL DISTRIBUTION PIPES MUST BE PLUGGED UNLESS INTERCONNECTED.
BOTTOM OF TRENCH TO BE LEVEL.


ABSORPTION TRENCH DETAIL

NOT TO SCALE

WATER SERVICE CONNECTION

*CONSTRUCTION OF POTABLE WATER UTILITIES AND CONNECTION TO THE TOWN OF WARREN, NEW YORK, SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE DEPARTMENT OF ENVIRONMENTAL CONSTRUCTION (DEC) AND THE REQUIREMENTS OF THE NYSDOH AND THE TOWN OF WARRENBORO.

WATER SERVICE LINE APPURTENANCES:



TYPICAL TRENCH
N.T.S.

SERVICE SADDLES, CORPORATION STOPS, CURB STOPS AND OTHER LINE APPURTENANCES TO BE PRODUCTS MANUFACTURED BY FORD. ALL PRODUCTS TO BE SUPPLIED BY A SINGLE SUPPLIER. THREADS FOR SERVICE LINE FITTINGS TO CONFORM TO STANDARD PIPE THREADS AND BE PROVIDED WITH A WING NUT AND WASHER. CURB BOXES TO BE EXTENSION TYPE SUPPORTED BY FOOT PIECE OR CONCRETE SUPPORT BLOCK. CORPORATION STOPS TO BE FORD TYPE PRO-CO THREAD WITH 1/2\"/>

DONALD SCHREIBER

*Minor Subdivision
for*
*Situate in the
Town of Warrenton Ulster County, New York*
Scale: 1\"/>

Job #3165

REVISION DATES:

Spencer S. Hall, Land Surveyor
NYS Lic. No.: 49138
6244 Route 82, Stonyfordville, NY 12587
(845) 868-1202

NOSEK ENGINEERING
2245 ALBANY POST ROAD
WALDEN, NEW YORK 12586
TEL: 845.926.7790

TEL: 845.926.7790